

LIST OF ON-GOING R&D PROJECTS OF CIL

[As on 12.01.2026]

Sl. No.	Name of the projects and its details	Date of start	Date of completion	Approved outlay [Rs. In lakh]
1	<p>Scaling up the conversion of CO₂ to methanol and other value-added chemicals with 500 Kg CO₂/day capacity. [Project code: CIL/R&D/04/14/2021]</p> <p>Implementing agencies: Jawaharlal Nehru Centre for Advanced Scientific Research (JNCASR), Jakkur, Bangalore; Singareni Collieries Company Limited (SCCL), Kothagundem, Telangana; and BREATHE Applied Sciences Pvt Ltd, Bangalore</p> <p>Objectives:</p> <ul style="list-style-type: none"> ❖ To develop an integrated technology for the conversion of CO₂ to methanol and other value added chemicals at industrial relevant scales having commercially viable conversion efficiencies. ❖ To develop end-to-end technology of thermo-catalytic CO₂ reduction by integrating 4 sub-technologies, which are (a) CO₂ capture, (b) Hydrogen generation, (c) Reduction of CO₂ and (d) Product purification. 	1st Oct. 2021	31 st October 2025	<p>1998.57 JNCASR-1998.57 SCCL - Nil</p>
2	<p>Development of tandem approach for Paste Fill Technology and extraction methodology by continuous miner (CM) deployment for Shyampur B Colliery of Mugma Area, ECL [Project code: CIL/R&D/04/18/2022]</p> <p>Principal Implementing Agency: ECL, Sanctoria</p> <p>Sub-Implementing Agency: CIMFR, Dhanbad</p> <p>Objectives:</p> <ul style="list-style-type: none"> ❖ Development of suitable paste backfill system. ❖ Development of suitable mining method in tandem with paste backfill. ❖ Subsidence monitoring and prediction for paste fill panels. ❖ Procurement, erection, commissioning and monitoring of paste backfilling system as well as the monitoring of mining methods, strata and surface. 	15 th Sept. 2022	30 th Sep. 2025	<p>4997.45 ECL: 4822.66 CIMFR: 174.79</p>

3	<p>Prototyping of Bi-facial Perovskite Module Leading to 4-T Perovskite-Si Tandem Structure.</p> <p>[Project Code: CIL/R&D/04/19/2023] Principal Implementing Agency: IIT Bombay</p> <p>Objectives:</p> <ul style="list-style-type: none"> ▪ Development of the Bi-Facial Perovskite Module Here a process is proposed to be developed to produce bi-facial perovskite modules of area 100 cm² to achieve ~ 20% efficiency at the module level and ~ 24% at the cell level with projected stability for ~ 10 years. The reliability of the devices will be measured as per the ISOS protocol. ▪ Implementation of the 4-Terminal tandem structure: It is expected a 4T Si-Perovskite tandem structure with a projected efficiency of >25% at the module level and >30% at the cell level. 	20 th July 2023	19 th July 2026	1770.00 IIT- Bombay:1770.00
4	<p>5G Captive Non-public Network for Integrated Voice, Video & Data Communication in Opencast Coal Mines (Project Code: CIL/R&D/05/03/2024) Implementing Agencies: ME Division, CMPDI (HQ), Ranchi & Centre for Development of Advanced Computing (C-DAC), Thiruvananthapuram</p> <p>Objectives: Prime aim of this project are setting up of 5G Captive</p>	24 th Jan. 2024	23 rd Jan. 2026	2406.54 CMPDI: 88.50 C-DAC. 2318.04
	Non-Public network at an opencast coal mine; Design, development and demonstration of 5G use cases (Digital twin of load haul dump operation, collision avoidance system, 5G drone based digital mapping and remote monitoring, 5G camera based traffic control, voice & video calls, surveillance & asset tracking, AR/VR application, environmental monitoring).			

5	<p>Design of Geotechnical structures for extraction of coal seam at higher depth using Continuous Miner</p> <p>Project code: CIL/ R&D/1/80/2024] Implementing Agency: NIT, Rourkela</p> <p>Sub implementing Agencies: RI-V, CMPDI, Bilaspur ,University of Wollongong, Australia & SCCL, Kothagudem</p> <p>Objectives:</p> <ul style="list-style-type: none"> ❖ To develop design norms for different geotechnical structures involved during CM based coal extraction at depth range of 200-600 m depth. ❖ Assessment and classification of rock mass based on available approaches on core procured from freshly drilled boreholes. ❖ Study of geotechnical structures' behaviour of the selected site through simulated models. ❖ Assessment of strata behaviour including underground structures through instrumentation and continuous monitoring during actual mining operation at the selected underground coal mines. ❖ Validation/comparison of simulated design with results of actual operation/field investigations in continuous miner/mechanised working at the selected site. ❖ To develop numerical models for design of geotechnical structures like pillar/coal block, cut-out distance, galleries, fender/rib/snook, applied supports including manner of pillar extraction by varying relevant parameters. ❖ To develop of design for stress management technique at higher depth of cover. ❖ To develop design norms for novel method of pillar/coal block extractionke Wongawilli/others by CM for the considered depth range. 	1 st July 2024	30 th June 2027	<p>303.38 NIT, Rourkela: 303.38 RI-V,CMPDI – Nil</p>
---	--	---------------------------	----------------------------	--

6	Development of Energy Efficient Ergonomically Designed (EEED) Chair Lift Man Riding System (Project Code: CIL/R&D/1/81/2024) Principal Implementing Agency: IIT-ISM, Dhanbad Sub Implementing Agencies: DGMS, Dhanbad & BCCL, Dhanbad Objectives: <ul style="list-style-type: none"> ❖ To develop a test rig of novel closed-loop Hydro Static Transmission (HST) system representing the power pack of chair lift man riding system. ❖ To analyze the energy consumption of the proposed closed-loop system with the conventional system. ❖ To analyze the whole-body vibration of a rider on a suitably designed test rig. ❖ To investigate outcomes of the above for feasible implementation of a newly designed chair lift system fit for use in steeply incline mine. This would greatly optimize on time utilization and render safety, comfort of workmen resulting in productivity enhancement 	1 st July 2024	30 th Jun. 2026	53.95
7	Study on post –mining accelerated reclamation in coal mining area using soil microbial community Project Code: CIL/R&D/04/21/2024 Principal Implementing Agency: CIMFR, Dhanbad Sub-implementing agency: BCCL, Dhanbad] Objectives: <ul style="list-style-type: none"> ❖ Isolation and screening of nutrient ❖ recycling soil microbial community from mining and nearby forest area. 	15 th Sep 2024	14 th Sep 2026	51.23 CIMFR:51.23 BCCL:NIL

	<ul style="list-style-type: none"> ❖ To develop microbial consortium to enhance soil nutrient cycle and soil fertility for accelerated plant growth. ❖ Ex-situ models to check the efficacy of microbial consortium to improve soil nutrient cycle. 			
8	<p>Assessment of coking coal quality with respect to active components present in coking coal.</p> <p>[Project code: CIL/R&D/03/04/2024] Implementing agencies: National Metallurgical Laboratory Jamshedpur; Central Mine Planning & Development Institute (CMPDI), Ranchi</p> <p>Objectives:</p> <ul style="list-style-type: none"> ❖ Identification and characterization of the active component in various coking coal. ❖ Isolation of active components in coking coal by physical separation. ❖ Characterization of vitrinite, inertinite, and reflectance of active components as well as in raw coking coal. ❖ Establishment of a correlation between active component and vitrinite, inertinite, and reflectance. ❖ Formulating a mathematical model to assess the coking coal quality with respect to the active component. 	20 th Dec 2024	19 th Dec 2026	195.64 NML: 62.21 CMPDI: 133.43
9	<p>Creation of research facilities for examining the mental state and improving mental health including dementia</p> <p>Project code: CIL/R&D/01/82/2024 Principal Implementing agency: IIT Mandi, Himachal Pradesh Sub implementing Agencies: CCL, Ranchi & CMPDI, Ranchi</p> <p>Objectives:</p> <ul style="list-style-type: none"> ❖ To develop research facilities for the early detection of mental health issues of the Indian population including mine workers and CIL employees. ❖ Health screening of mining workers entering mines based on their mental health. ❖ To develop neuro feedback-based interventions for faster cognitive enhancement. 	20 th Dec 2024	19 th Dec 2026	333.56 IIT Mandi:333.56 CCL:Nil CMPDI:Nil
10	<p>Carbon electrode based indigenous low-cost perovskite solar cells development</p> <p>Project Code:CIL/R&D/04/22/2025</p> <p>Implementing Agencies: Indian Institute of Technology,</p>	01 st May 2025	30 th April 2027	492.05 IIT,Roorkee: 456.65 NaCCER:35.40

	Roorkee; NaCCER, CMPDIL, HQ, Ranchi Objectives: ❖ Fabrication and advance characterization of carbon electrode. ❖ Fabrication of high efficiency HTL-free carbon-based PSC. ❖ Cost benefit analysis of the perovskite module. ❖ Demonstration of prototype in IITR			
11	Indigenous Development of IoT-Enabled Technology for Monitoring, Analysis and Interpretation of Longwall Shield Pressures for Improving Safety and Productivity (Phase-II, TRL 5 to 8) Project Code: CIL/R&D/01/84/2025 Implementing Agencies: NaCCER, CMPDI, HQ, Ranchi; Indian Institute of Technology (IIT), Kharagpur and Eastern Coalfields Limited (ECL) Sanctoria Objectives: ❖ To develop a comprehensive system for monitoring the entire longwall panel's shield pressure and shearer position. Pressure sensors will be installed in all shields of the longwall panel, and position sensors at strategic positions will be integrated into designated shields to collect shearer position data every 60 seconds. ❖ The master data acquisition system (MDAS) will be placed at a suitable location on the energy trolley so that the length of the RS485 cable can be shorter and the problem of moving the MDAS trolley can be eliminated. In other words, the layout of the entire system is in a compact form. ❖ Effective layout mechanism of the communication and power cables at the longwall face such that they do not get cut or disturbed due to the movement of shields. ❖ Upgrading the software for data collection and early forecasting of periodic roof weighting, shield leakage, and other maintenance information	01 st May 2025	30 th April 2027	337.06 NaCCER: 92.93 IIT KGP: 244.13
12	Development of an Indigenous Optical Fiber Based Instrument for Measuring In-The-Hole Velocity of Detonation (VOD) and Analyze the Performance of Explosives & Accessories in Field Condition (Phase-II, TRL 5 to 8/9) Project Code: CIL/R&D/01/85/2025	01 st May 2025	30 th April 2026	282.30

	<p>Implementing Agencies: NaCCER, CMPDI, HQ, Ranchi; Blasting Division, CMPDIL HQ, Ranchi, Regional Institute – VI, CMPDI Singrauli</p> <p>Objectives:</p> <ol style="list-style-type: none"> 1. Technical Objectives: <ul style="list-style-type: none"> • Enhance the instrument's robustness, accuracy, and reliability for operational deployment. • Validate the system's performance under real-world explosive conditions in confined environments. • Optimize the automated reporting software to comply with industry standards and user requirements. 2. Operational Objectives: <ul style="list-style-type: none"> • field trials to confirm system performance and reliability. • Initiate the certification processes for deployment in hazardous and explosive environments. 3. Commercial Objectives: <ul style="list-style-type: none"> • Refine the prototype for scalable manufacturing • Develop end-user training, documentation, and maintenance support systems 			
13	<p>Automation, Control & Wireless Communication in Underground Mines on 4GLTE/5G ready Communication Network in Jhanjhra Mines ECL.</p> <p>Project Code: CIL/R&D/05/04/2025 Principal Implementing Agency: M/s Indian Telephone Industries (ITI Ltd.), Lucknow</p> <p>Sub-Implementing Agencies: (i) Mine Electronics (ii) NaCCER, CMPDI, Ranchi.</p> <p>Objectives:</p> <ul style="list-style-type: none"> ❖ To establish 4G LTE/5G Ready Communication Network in the Underground Coal Mines. ❖ To provide seamless voice and video communication between underground workers and control centres using 5G CNPN/4G LTE ❖ To automate conveyor belts, pumps, and other critical systems to enhance operational efficiency and reduce manual intervention 	15 th June 2025	14 th June 2027	2184.91 ITI (L):1992.93 ME Deptt: 111.74 NaCCER: 80.24

	<ul style="list-style-type: none"> ❖ To deploy IoT-based sensors for monitoring gases (CH₄, CO₂), temperature, humidity, and air velocity inside the mine ❖ To implement an asset and miner tracking system for improved safety and resource management. 			
14	<p>A Pilot Project on Underground Coal Gasification (UCG) to establish technology in Indian geo-mining conditions -Phase-2</p> <p>Project Code No: CIL/R&D/04/23/2025</p> <p>Principal Implementing Agencies: CMPDIL HQ Ranchi and ECL Sanctoria</p> <p>Sub-Implementing Agency: Ergo Exergy Technologies Inc, Montreal Qc, Canada</p> <p>Objectives:</p> <ul style="list-style-type: none"> ❖ Development of detailed design of the UCG Pilot Plant, construction, commissioning, operation and controlled shutdown, followed by post-shutdown monitoring. The final feasibility study report on UCG Pilot Plant operation with suitable recommendation for commercial operations will be submitted at the end. 	20 th June 2025	19 th Sep 2026	<p>4839.32 EETI, Canada:4076.63, CMPDI, Ranchi:193.77, ECL, Sanctoria: NIL;</p> <p>Forex conversion charges/other taxes:568.92</p>
15	<p>Revolutionizing Mine Safety: An AI-Enabled Fire Detection System for Underground Active and Closed/Abandoned Mines</p> <p>Project Code No: CIL/R&D/01/86/2025</p> <p>Principal Implementing Agency: Indian Institute of Engineering Science and Technology (IIST), Shibpur.</p> <p>Sub-Implementing Agencies: Milieu Global IT Solutions Pvt Ltd., Hyderabad & CCL Ranchi</p> <p>Objectives:</p> <ul style="list-style-type: none"> ❖ Identification and installation of gas and video monitoring stations at different locations of active and closed/abandoned underground mines and acquisition of real-time gas concentration levels and videos. ❖ Prediction of the likelihood and intensity of fire hazards at different locations of active and abandoned/closed underground mines, using deterministic and probabilistic, crisp and fuzzy time series forecasting (TSF) of gas concentration levels, leveraging AI-driven models, including machine learning, deep learning and hybrid models on real-time gas sensor data ❖ Detection of the ongoing or imminent fire incidents 	10 th Aug 2025	09 th Aug 2027	<p>420.74 IIEST:53.99 MGISPL: 366.75</p>

	and other abnormal situations in active and abandoned/closed underground mines, using AI models, especially computer vision and deep learning models.			
--	---	--	--	--

16	<p>Sustainable Solutions for Removal of Fluoride from Groundwater in Mining Area of Col India Ltd in Jharkhand, Odisha and West Bengal for Safe Drinking Water, Phase-I</p> <p>Project Code No: CIL/R&D/04/24/2025 Principal Implementing Agency: CSIR- Institute of Minerals and Materials Technology (IMMT), Bhubaneswar</p> <p>Sub-Implementing Agencies: Reseapro Scientific Services Private Ltd; CMPDI Regional Institute RI-VII, Bhubaneswar; Regional Institute RI-III, CMPDI, Ranchi</p> <p>Objectives: The broad objective is to conduct R&D intervention comprising of sampling and analysis from random sites within certain radius around the coal mining areas in phase-1, and then implement the fluoride removal technological solutions developed in phase-1, in the high fluoride contamination areas in the CIL operational areas in the State of Jharkhand, Odisha and West Bengal. This will be accomplished through the following detailed activities: Phase-1</p> <ol style="list-style-type: none"> 1. Contamination Assessment <ul style="list-style-type: none"> • Identify fluoride contamination sources in different regions in mining areas of Coal India Limited's operations. • Conduct water sampling and lab analysis. 2. Development & Optimization of fluoride Removal Methods <ul style="list-style-type: none"> • Adsorption-based techniques: Activated alumina/ nano alumina, activated carbon, etc. • Electrolytic Defluoridation (EDF) for cost-effective treatment. 	1 st Sep 2025	31 st Aug 2026	1291.06 IMMT:318.10 CSIR:884.21 RI VII, CMPDI, BHUBANESHWAR: 44.37 RI-III, CMPDI, RANCHI:44.37
-----------	---	--------------------------	---------------------------	---

	<ul style="list-style-type: none"> Modification of the terafil filter cartridge with fluoride adsorbent materials. <p>3. AI/ML Integration for Water Quality Assessment and Fluoride Contamination Monitoring</p> <ul style="list-style-type: none"> IoT-Enabled Sensor Kits: Continuous real-time measurement of critical water quality parameters including fluoride concentration, pH, TDS, turbidity, and volumetric flow rate. Geo-Spatial Tagging: Each sampling point will be GPS-mapped to enable location-accurate trend monitoring and longitudinal data analysis. AI/ML Dashboard: A cloud-integrated digital platform will serve as the central command center for predictive modeling, trend detection, and risk-level classification. 			
17	<p>Non-Invasive Health Screening and Smart Monitoring Systems for Coal Miners' Safety and Well-being</p> <p>Project Code No: CIL/R&D/01/87/2025</p> <p>Principal Implementing Agency: Indian Institute of Engineering Science and Technology, Shibpur (IEST)</p> <p>Sub-Implementing Agencies: ECL, Sanctoria</p> <p>Objectives:</p> <p>Non-Invasive Oral and Lung Carcinoma Screening in Coal Miners with Occupational Exposure Using Electronic Bio Sensing Systems.</p>	10 th Sep 25	09 th Sep 27	<p>470.57</p> <p>IEST: 470.57</p> <p>ECL, Sanctoria: Nil</p>